



**A PRINTED COPY OF ALL APPROVED DOCUMENTS MUST REMAIN ON
THE JOB SITE AND BE AVAILABLE AT ALL TIMES FOR INSPECTORS.**

UTILITIES

**CITY OF BELLEVUE
UTILITIES DEPARTMENT
ENGINEERING DIVISION
APPROVED**

DATE APPROVED: 07/17/2025
APPROVED BY: JEHenderso
JEHENDERSO@BELLEVUEWA.GOV

PERMIT NUMBER: 25-116539 UA
PROJECT NAME: New SFR
SITE ADDRESS: 3039 Bellevue Way NE

Check Permit Status

<https://PermitSearch.MyBuildingPermit.com>



Share your feedback!

On your plan review experience:
<https://bellevuewa.gov/IssuedSurvey>

On your inspection experience:
<https://bellevuewa.gov/InspectionSurvey>


Request an Inspection

By phone: (425) 452-6875

On line: <https://Inspection.MyBuildingPermit.com>



Issued 07/23/2025



87°03'39" W 231.22'

Here is where the existing Sewer Line is, where we are planning to connect the new sewer line.

Line 1 – From Rear of the House to Y-Connector:

The sewer line coming out of the house began with a 3" pipe, which we transitioned to 4". We installed a 22½° elbow fitting, then dropped one foot into the trench and added another 22½° elbow. Following that, we installed a cleanout, added a 3-foot section of pipe, a 45° elbow fitting, a 10-inch pipe, and another 45° elbow. This was followed by 40 linear feet of 4" pipe leading into a 4" Y-connector. This section of the line maintains a consistent 2% slope toward the Y-connector.

Main Line – From Y-Connector to Existing SUR Connection:

From the Y-connector, we continued with 4 feet of pipe, followed by a 45° elbow, then 12 feet of pipe. We installed two 22½° elbow fittings, then a 16-inch pipe section, another 45° elbow, and 3 more feet of pipe before placing the final cleanout. The line then transitions from PVC back to the existing 4" ABS pipe to connect to the main SUR line. This final segment maintains a 3% slope from the Y-connector to the SUR connection.

Line 2 – From Front Door Entry to Y-Connector:

The pipe coming from the front door entry is 4" ABS. We transitioned it using a Schedule 80 fitting to connect to PVC. After installing a cleanout, we placed a 45° elbow fitting 6 inches away, followed by a 13-foot run of pipe that connects to the same Y-connector. This branch of the system has a 3% slope leading to the Y-connection.

Side Sewer Permit General Conditions

1. The Utility Codes and Engineering Standards shall be complied with fully and completely, and are included by reference as part of this permit. (Utilities Engineering Standards can be purchased in City Hall at Service First or found on-line at www.bellevuewa.gov. Select "Find" "City Codes and Documents" >>> "Standards and Guidelines" >>> "Utilities Engineering Standards" >>> "Current Sewer Engineering Standards.") Issuance of the permit and acceptance by the property owner (Owner), his designated agent, or his contractor shall be construed as evidence that Owner and his contractor has read the same and agree to its terms and stipulations in their entirety.
2. Information provided by the City of Bellevue in the form of system as-builts or side sewer drawings is based on the best available information. It is not guaranteed to be accurate. All information should be field verified prior to construction. Call 811 before you dig for utility locations. The City assumes no responsibility for improper locations or failure to show utility locations on the approved plans.
3. Owner agrees to maintain the portion of side sewer lying outside the public right-of-way, in accordance with the rules and regulations of the City of Bellevue. Owner will permit access by authorized representatives of the City of Bellevue on the property described in the application at any reasonable time for the purpose of inspection for compliance with City of Bellevue regulations.
4. Contractor and Owner(s) shall protect, defend, indemnify, and save harmless the City, its officers, employees and agents from any and all costs, claims, judgments or awards of damages, arising out of or in any way resulting from the negligent acts or omissions of the Contractor, its officers, employees, and agents.
5. Owner shall keep on the construction site during the progress of work a competent superintendent and any necessary assistants, all to the satisfaction of the City of Bellevue. The superintendent shall represent Owner in his absence and all directions given to the superintendent shall be as binding as if given to Owner.
6. Owner and his contractor shall safeguard the work done under this permit in such a manner as to prevent injury and/or damage to public or private property and to the municipal sewer system. Whenever it is necessary in the course of construction to remove or disturb culverts, landscaping, driveways, roads, pipelines, monuments, property stakes or other existing improvements, whether public or private, they shall be replaced to a condition equal to that existing before they were so removed or disturbed.
7. Owner's contractor shall take all necessary precautions for the safety of employees on the work site and shall comply with all applicable provisions of federal, state, county and municipal law with regard thereto. Contractor shall erect and properly maintain at all times, as required by the conditions and progress of the work, all necessary safeguards for the protection of employees and the public.
8. No backfilling shall be done until the sewer facilities have been inspected, tested and approved by the Utilities Inspector. If any work is covered without the approval or consent of the Utility, it shall be uncovered for inspection at no cost to the Utility. All pipe shall be bedded in 5/8-inch minus crushed rock. **Do NOT use pea gravel.** All excavations within the right-of-way shall be backfilled with 5/8-inch minus crushed rock to finished subgrade. A compaction test report shall be provided to the inspector.
9. Contractor shall arrange a time to accompany the Utilities Inspector on the final inspection and subsequent re-inspection, if required. Deficiencies discovered during the final inspection shall be corrected within **seven (7) days** of notice thereof, and in no instance, shall service be provided until the deficiencies are corrected and the work passes re-inspection.
10. This permit includes a limited amount of inspection time, including travel, as-built drawing review and processing. Time spent over that allowed in the permit will be billed to the person designated on the "Bill To" form. Failure to pay will result in the bill being sent to collections. Inspections by other jurisdictions, related to the sewer work, will also be billed to the person designated on the "Bill To" form.
11. For single family residential connections, sewer hole-cuts (6-inch minimum diameter) on 8-inch diameter and larger, concrete, metallic and clay pipe shall be performed by a qualified coring contractor at the Owner's expense in the presence of the Utilities Inspector. Contact Bellevue Utilities at 425-452-6875 to schedule an inspection appointment 48 hours in advance (not including weekends and holidays). Use a Romac Style "CB" Sewer Saddle (6-inch dia.) to complete the connection to clay, concrete and DI sewer mains (8-inch min. dia.). PVC mains require a new PVC side sewer tee to be cut in.

Cores shall be made at the 10 o'clock or 2 o'clock positions. The pipe coupon shall be provided to the Utilities Inspector. The cored hole shall be free of lips, burrs and other defects that may catch debris. Jagged, non-circular, improperly sized and/or mis-located cores and cracked or otherwise damaged pipe sections shall require that the damaged pipe section be replaced with a PVC tee and mechanical, Romac-style transition couplings on concrete, metallic and clay pipe, and rigid PVC couplings on PVC pipe. Flexible rubber couplings (e.g. Fernco and Caulder couplings) are not allowed on the sewer main or the 6-inch side sewer lateral.

12. When work is to occur in existing easements, the contractor shall notify the easement grantor and Bellevue Utilities in writing a minimum of 48 hours in advance of beginning work. Failure to notify grantor and Bellevue Utilities will result in a Stop Work Order being posted until the matter is resolved to the satisfaction of Bellevue Utilities. A written release from the easement grantor for the restoration of the easement area shall be furnished to the Utilities Inspector prior to permit sign-off.



Relining Private Side Sewers and Storm Drain Pipes

Supplemental Conditions

Revised January 6, 2017

General

Pipe lining, also known as Cured-In-Place Pipe (CIPP), is an allowable method for the repair of side sewers and storm drains using materials compatible with the diameter and type of the existing pipe. Unless otherwise specified below, side sewers and storm drain pipes installed by the trenchless methods shall conform to the requirements set forth in the Utilities Engineering Standards.

The contractor performing the proposed rehabilitation work shall have a current license agreement with the product manufacturer/assembler and shall have such license available to the Utilities Inspector. Additionally, the individuals performing the rehab work shall be certified by the product manufacturer/assembler.

Since the Owner is opting to use trenchless methods to rehabilitate the existing pipe, it is not possible to make significant adjustments in line and grade. The Owner accepts the fact the pipe may have less than minimum pipe slope and that there may be swales in the pipe grade. These deficiencies may require more frequent pipeline maintenance by the Owner.

Materials

Pipes on Private Property

Pipe lining materials for side sewers and storm drains must conform to current ASTM F1216, Standard Practice for Rehabilitation of Existing Pipelines and Conduit by Inversion and Curing of a Resin-Impregnated Tube. Pipe lining installation shall be in accordance with the requirements of the product manufacturer/assembler and as directed by their technical representatives.

Side Sewer and Storm Drain Laterals in the Right of Way or Public Easements

Side sewer and storm drain laterals in the Right of Way or in public easements shall conform to the requirements set forth in the Utilities Engineering Standards. Within the Right of Way or within a public easement, the minimum pipe size shall be 6 inch diameter.

Construction Methods

When installing the liner in the existing host pipe, bends may not exceed the minimum bend radius for size and thickness of the liner being installed. This may require the existing pipe bends to be excavated into order to provide for the minimum bend radius.

Prior to pipe rehab work, the existing (host) pipe must be cleaned, root cut, jetted, rodded, and/or otherwise cleaned to a condition that allows for rehab work to be effective per the manufacturer's recommendations.

Required Inspections

1. The contractor shall request all inspections that apply to work being performed prior to backfilling including by not limited to: a) fittings and connections; b) clean-outs; and c) check valves (when required).
2. The contractor shall request a pre-installation inspection (630 – Side Sewer; 635 – Storm Connection). A CCTV video inspection of the host pipe after cleaning operations shall be made and viewed by the Inspector prior to installing the liner. A copy of the CCTV inspection shall be provided to the Inspector on a DVD.



City of Bellevue
Utilities Department

3. The contractor shall request a post-installation inspection (630 – Side Sewer; 635 – Storm Connection). After running water through the rehabilitated pipe, a CCTV inspection of the pipe shall be made with the Inspector present and a copy of the video inspection on a DVD shall be furnished to the Inspector. The video shall meet acceptable standards and provide proper speed of the camera and sufficient lighting to enable a thorough visual inspection of the entire rehabilitated pipe including all connection points.
4. The contractor shall demonstrate to the Utilities Inspector via the LIVE video inspection that the pipe liner does not protrude into the city's lateral (6 inch dia.), the main or joint use pipe after completion of the work. If the pipe liner does protrude into the city's lateral, main or joint use pipe, the contractor shall trim the protrusion flush with surface, or otherwise eliminate the protrusion. If the Utilities Inspector is unable to verify that the pipe liner does not protrude in to the main or joint use pipe, the contractor shall video inspect the main or joint use pipe so that an affirmative determination can be made.
5. The contractor shall update the as-built drawing for the property with the location of the beginning and end of the liner and any new appurtenances added (e.g. a clean out to grade). The updated as-built drawing shall be provided to the Inspector at the final inspection (647 – Sewer Final; 648 – Storm Final).
6. For deficiencies (e.g. ponding, constrictions, kinks, and wrinkles), the contractor shall make the Owner aware of the deficiencies and the risks they pose. A written copy of such notification shall be provided to the Inspector at the final inspection (647 – Sewer Final; 648 – Storm Final).



Pipe Bursting Private Side Sewers and Storm Drain Pipes

Supplemental Conditions

Revised January 6, 2017

General

Unless otherwise specified below, side sewers and storm drain pipes installed by the trenchless methods shall conform to the requirements set forth in the Utilities Engineering Standards.

Since the Owner is opting to use trenchless methods to rehabilitate the existing pipe, it is not possible to make significant adjustments in line and grade. The Owner accepts the fact the pipe may have less than minimum pipe slope and that there may be swales in the pipe grade. These minor deficiencies may require more frequent pipeline maintenance by the Owner.

Materials

Pipes on Private Property

Contractor shall verify the appropriate Dimension Ratio of the High Density Polyethylene (HDPE) pipe to be used with his/her engineer. The minimum dimension ratio shall be 26.

Outside of the Right of Way or public easement, the minimum pipe size for gravity lines shall be 4-inch diameter. Joint use pipes must be a minimum 6-inch diameter.

All HDPE fittings shall be factory fabricated.

The connection between the HDPE side sewer and the house clean-out at the foundation shall be made with a size-on-size mechanical transition coupling, such as a Romac 501-style coupling, Fernco "Strongback"-style coupling, or a long pattern DI sleeve, in conjunction with an internal stainless steel stiffening sleeve. Flexible rubber couplings (e.g. standard Fernco and Caulder couplings) are not allowed.

For storm drain pipes, the connection between the HDPE pipe and the existing drain pipe shall be made with a size-on-size mechanical transition coupling, such as a Romac 501-style coupling, Fernco "Strongback"-style coupling, or a long pattern DI sleeve, in conjunction with an internal stainless steel stiffening sleeve. Flexible rubber couplings (e.g. standard Fernco and Caulder couplings) are not allowed.

Side Sewer and Storm Drain Laterals in the Right of Way or Public Easements

Side sewer and storm drain laterals in the Right of Way or in public easements shall conform to the requirements set forth in the Utilities Engineering Standards. Within the Right of Way or within a public easement, the minimum pipe size shall be 6 inch diameter. Pipe material shall be PVC (SDR 35 minimum).

For side sewers, the connection between the HDPE side sewer and the 6-inch side sewer lateral shall only be made with a size-on-size mechanical coupling, such as a Romac 501-style coupling, a gasketed long pattern sleeve, or a 6-inch Fernco-style bell donut adapter. Flexible rubber couplings (e.g. Fernco and Caulder-style couplings) are not allowed.

Continue with a 6-inch diameter PVC nipple, a 6" x 4" PVC reducer, 4-inch diameter PVC nipple, a 4-inch PVC test tee, a 4-inch PVC nipple and then: 1) mechanical transition coupling, such a Romac 501-style coupling, or 2) a gasketed long pattern DI sleeve or, 3) a Fernco "Strong Back"-style coupling.

For storm drain laterals 6 inches in diameter and larger, the connection to the lateral shall only be made with a size-on-size mechanical transition coupling, such as a Romac 501-style coupling, or 2) a gasketed long pattern DI sleeve, or 3) a Fernco-style bell donut adapter and a PVC nipple. Flexible rubber couplings (e.g. Fernco and Caulder-style couplings) are not allowed.



City of Bellevue
Utilities Department

Construction Methods

Hole cuts or taps shall not be allowed on HDPE pipe. All connections shall be made with factory fabricated fittings.

HDPE pipe may be joined by butt fuse welding or by electro-fuse couplings to produce a water-tight, air testable connection.

When installing HDPE pipe through the existing host pipe, bends may not exceed the minimum bend radius for size and dimension ratio of the HDPE being installed. This may require the existing pipe bends to be excavated into order to provide for the minimum bend radius.

For side sewer slopes of 2% or less, the interior bead at butt fuse welded joints shall be removed to minimize the potential of debris accumulation. Interior bead removal is recommended for pipes with slopes greater than 2% for the same reason. Take precautions to prevent "rifling" of the HDPE pipe.

Installation Strain and Temperature Effects - Due to pipe bursting strain and/or temperature effects on high density polyethylene (HDPE) pipe during installation, the HDPE pipe will be required to rest for at least 24 hours or as long as recommended by the manufacturer, whichever is longer, prior to final pipe cutting to allow the HDPE pipe to achieve equilibrium. No pipe connections or anchoring shall be made prior to the expiration of the rest period.

Thermal Expansion - High Density Polyethylene (HDPE) has a high coefficient of thermal expansion. The installation of a HDPE pipe must take into account the expansion and contraction of the pipe material so that pipe separation at the couplings does not occur. This shall be accomplished by installing pipe anchors within three (3) feet of the connecting coupling.

Required Inspections

1. The contractor shall request all inspections that apply to work being performed prior to backfilling including by not limited to: a) all pipe anchors, bends, fittings and connections; b) clean-outs; and c) check valves (when required).
2. The contractor shall request a pre-installation inspection (630 – Side Sewer; 635 – Storm Connection). A CCTV video inspection of the host pipe after cleaning operations shall be made and viewed by the Inspector prior to pipe bursting. A copy of the CCTV inspection shall be provided to the Inspector on a DVD.
3. The contractor shall request a post-installation inspection (630 – Side Sewer; 635 – Storm Connection). After running water through the rehabilitated pipe, a CCTV inspection of the pipe shall be made with the Inspector present and a copy of the video inspection on a DVD shall be furnished to the Inspector. The video shall meet acceptable standards and provide proper speed of the camera and sufficient lighting to enable a thorough visual inspection of the entire rehabilitated pipe including all connection points.
4. If the pipe appears to be out of round, the Inspector may require the standard mandrill to be pulled through the pipe. If the mandrill will not pass, that portion of the pipe may need to be repaired as determined by the Inspector.
5. The contractor shall update the as-built drawing for the property with the location of the beginning and end of the new pipe, connection details and any new appurtenances added (e.g. a clean out to grade). The updated as-built drawing shall be provided to the Inspector at the final inspection (647 – Sewer Final; 648 – Storm Final).
6. For deficiencies (e.g. ovalization, ponding, kinks, and wrinkles), the contractor shall make the Owner aware of the deficiencies and increased maintenance risk they pose. A written copy of such notification shall be provided to the Inspector at the final inspection (647 – Sewer Final; 648 – Storm Final).



City of Bellevue
Utilities Department

Scheduling Inspections For UA, UB and BS (Storm Drainage) Permits

January 6, 2017

Scheduling Utilities Inspection

Utility inspections for UA, UB and BS (storm drainage only) permits can be scheduled via the IVR system (425-452-6875) or MyBuildingPermit.com (MBP). Inspection requests should use the following codes:

UA	630 Side Sewer	647 Sewer Final
UB	635 Storm Connection	648 Storm Final
BS	635 Storm Drainage	648 Storm Final

The cut-off time for same day inspections will be 4:30 AM, just like other City of Bellevue inspection groups. Up to the cut-off time, you can request an inspection for the same day or make an inspection request for one or two days out.

You will receive a call between 7 AM and 8 AM to schedule an inspection appointment for the current day between 9:00 AM and 2:30 PM, or confirm the date and appointment time for future date. Customers will be called back in the order received. If we are unable to make voice contact, we will leave a message at the contact number provided and move to the next requestor.

If we are unable to make voice contact with you after three (3) calls between 7 AM and 8 AM, the third voice mail message will note that the inspection request is canceled. You will need to call 425-452-6875 or go to MyBuildingPermit.com to request another inspection for the following business day.

There may be high volume days, such as the Thursday before a holiday weekend, where the inspection demand will exceed our capacity. Popular time slots (early afternoon) may have been booked days in advance by some contractors who are scheduling their inspection appointments ahead. You will have to be scheduled for the next available appointment time which may be the following business day.

Cancellations

Customers may use IVR or MBP.com after hours to cancel inspection requests up to the 4:30 AM cut-off for the same day inspection. After the 4:30 AM cut-off, customers must call 425-452-6875 during business hours (8 AM to 4 PM) to speak with a representative in order to cancel inspections.

Customers may cancel appointments up to 2 hours prior to the inspection appointment without incurring any inspection fees. Two hours advance cancellation allows us to try as schedule an inspection appointment in place of the cancellation. The intent is to be able to provide inspections to all who need them.

For cancellations within the two hour period prior to the appointment, you may be assessed a re-inspection fee if: 1) there has been a previous late cancellation; or 2) customers who were deferred to the next business day were not able to be given sufficient notice so that they could take advantage of the cancellation.

Customers who cancel the appointment while the inspector is en route, who cancel on site, or who are not ready for inspection when the inspector arrives, will be charged a re-inspection fee.

Thank you for your cooperation as we work to provide you with inspection scheduling options that are convenient and flexible.



Issued 07/23/2025

Side Sewer As-built/Inspection Procedure

Outlined below is the general procedure for having a side sewer inspected and approved by the City of Bellevue Utilities Department. A more thorough discussion of side sewer standards and requirements may be found in Chapter S6 of the Utilities Engineering Standards Handbook. Please note: it is the side sewer permit applicant's responsibility to prepare a neat and accurate side sewer as-built drawing **before** the side sewer inspection.

Permit Issuance

Permit Center staff will issue a side sewer permit with standard side sewer construction conditions, sewer grid map, a blank as-built drawing, an as-built drawing checklist, and a sample drawing. The side sewer applicant will be reminded by staff that a neat and accurate storm drain connection as-built drawing must be prepared.

Inspection Appointment

The side sewer permit applicant shall call the Inspection Request Line (425-452-6875) to schedule an inspection of the completed work. When a property owner or contractor calls to make a side sewer inspection appointment (at least 24-hours in advance), they will be reminded again that a neat and accurate side sewer as-built drawing must be prepared.

Site Inspection

Upon entering the site, the Utilities Inspector will request the completed as-built drawing. If an as-built drawing has not been prepared, the inspection may proceed; however, the permit cannot be signed off during this inspection. The Inspector will inform the contractor/property owner that another inspection will be required. Hourly inspection charges will apply to this and every subsequent inspection including any follow-up required to obtain the as-built drawing. The contractor/property owner shall request another inspection appointment via the Inspection Request Line after a suitable as-built drawing has been prepared.

If an as-built drawing has been prepared, the Inspector will first review the drawing for compliance with the as-built drawing checklist. Sloppy, dirty, incomplete and/or inaccurate drawings will be **rejected**. The Inspector will inform the contractor/property owner that the drawing does not comply with the requirements. The inspection may proceed; however, the permit cannot be signed off during this inspection. The Inspector will inform the contractor/property owner that another inspection will be required. Hourly inspection charges will apply to this and every subsequent inspection including any follow-up required to obtain the as-built drawing. The contractor/property owner shall request another inspection appointment via the Inspection Request Line after a suitable as-built drawing has been prepared.

If an acceptable side sewer as-built drawing has been prepared, the Inspector will verify the dimensions and material call-outs, check the connections to the sanitary sewer system and building plumbing (if installed), and performance test the side sewer. If the side sewer passes, the permit will be finalized and the side sewer approved for use.

If the side sewer fails the performance test or has other deficiencies, the Utilities Inspector will inform the contractor/property owner to correct the deficiencies and inform him that another inspection will be required. A Correction Notice may be posted. The Inspector will inform the contractor/property owner that at least one (1) hour of inspection time will be logged against the permit for this visit. Any subsequent inspection will be charged a **minimum** of 1.0 hours.

Please note that most side sewer permits include about one hour of field inspection time (one site visit). Any additional inspection time will be billed to the person designated on the "Bill To" form. Failure to provide an acceptable side sewer as-built drawing in a timely manner so that the side sewer can be approved for use will result in a delay in the approval



for occupancy.



Side Sewer As-built Drawing Checklist

It is the property owner/contractor's responsibility to provide a complete and legible as-built drawing.

All lettering and drafting must be neat and legible. Wet, dirty, damaged, incomplete or poor quality drawings will be rejected. All lettering must be large enough to be read after microfilming and be orientated with the North arrow, reading left to right. A sample side sewer as-built drawing is included on the back of this page for your reference.

The drawing shall include the following:

- _____ North Arrow
- _____ Adjacent Street Name(s) and/or Number(s)
- _____ Sewer Main with flow direction arrows
- _____ Upstream MH with number (from Utility grid map)
- _____ Downstream MH with number (from Utility grid map)
- _____ Property - R/W Line
- _____ Full building/house foundation outline with house number
(Show entire foundation outline. Omit overhangs and awnings)

Side Sewer Stub

- _____ Stub stationing in feet from next downstream SSMH (_+ _____)
- _____ Length/Diameter/Material Type
- _____ Depth at Property - R/W Line

Side Sewer

- _____ Stub to side sewer fitting/reducer - depth, size and material
- _____ Inspection tee - depth, size and material
- _____ Side sewer pipe - lengths, diameters, and material
- _____ Side sewer bends and fittings - diameters, type and material
- _____ Clean-outs - depth, diameter, fitting types and material
- _____ Tie dimensions to end of provided stub, building connection and clean-outs
from fixed/permanent references such as building corners (no trees, stumps,
fire hydrants, power poles, etc.).
- _____ Pipe depth at building connection



Issued 07/23/2025

ÆB"·., SIDE SEWERAS-BUILT yt/ÂÂ,,

ADDRESS _____


CONTRACTOR _____

DATE PERMIT ISSUED 12-31-99

DATE APPROVED _____

PERMIT NO. 99-997336 UADRAWN BY e O No x S

BY _____

COMMERCIAL OR OMESTJOINT USE: YES N

HOW TESTED: AIR

WATER OR

DIST FROM MH. NO. -1 TO TEE _____ FT.LEGAL DESCRIPTION: YDENBAUER A 00i TioDEPTH OF SEWER MAIN AT THE 8.5 FT.

DEPTH OF SIDE SEWER AT PROPERTY LINE _____ FT.

BASEMENT: YES (NO) BASEMENT CONNECTION: YES (NO)DEPTH OF PIPE AT HOUSE CONNECTION 2 FT.K.C. TAXE A 9 o ">+ a 4 Y

CONC DI OTHER _____

C.O.B. GRID NO. _____

EOFFIPü _____

CONNECTION AT MAIN: CUT IN TEE HOLE CUT EX ST STU



Issued 07/23/2025



SIDE SEWER AS-BUILT

ADDRESS _____ CITY _____ PERMIT NO. _____
CONTRACTOR _____ LIC. NO. _____ DRAWN BY _____
DATE APPROVED _____ BY _____

DIST FROM MH. NO. _____ TO TEE _____ FT.
C.O.B. GRID NO. _____
DEPTH OF SIDE SEWER AT PROPERTY LINE _____ FT.
DEPTH OF PIPE AT HOUSE CONNECTION _____ ft.

COMMERCIAL OR DOMESTIC _____ JOINT USE: YES NO
BASEMENT CONNECTION: YES NO DONE KNOW
HOW TESTED: AIR _____ WATER _____
CONNECTION AT MAIN: CUT IN TEE HOLE CUT EXIST. STUB

